



Ben C. Gerwick, Inc.

NEWS





Ben C. Gerwick, Inc. NEWS

Published by

Ben C. Gerwick, Inc.
http://www.gerwick.com/

601 Montgomery St., Suite 400
San Francisco, CA 94111
Tel: (415) 398 8972
Fax: (415) 433 8189

1300 Clay St., Suite 600
Oakland, CA 94612
Tel: (510) 464 8037
Fax: (510) 763 9004

112/114 J Street, Suite 200
Sacramento, CA 95814
Tel: (916) 442 8696

for its employees, affiliates and friends.
Please contact the President for permission to reprint articles.
© 1998 Ben C. Gerwick, Inc. All rights reserved.

Editorial Board

Ben C. Gerwick, Jr.
Paul E. Bach

Editorial Staff

Paul E. Bach	Ben C. Gerwick, Jr.
John M. Vincent	Dale E. Berner
George C. Fotinos	Robert B. Bittner
Matthew Dry	Yu-Yi Hsu
Thomas Dahlgren	Stephen P. Hardy

Cover Picture

Bath-Woolwich Bridge Foundation Construction

Contents

Completion of Presidio Viaduct — Siesmic Retrofit

By John M. Vincent

Bath-Woolwich Bridge — Floating Cofferdams

By Robert B. Bittner

Monongahela River - Dam 2 — Float-in Dam Construction

By Robert B. Bittner

Llagas Creek Bridge Replacement — Staged New Construction

By John M. Vincent

LNG Storage — Floating Concrete Structures

By Dale E. Berner

New Publications and Presentations

Ports '98 (Long Beach, CA);
***Design of New Wharf
Expansion for the Port of
Port Arthur, Texas,***
by George C. Fotinos,
Yu-Yi Hsu, Saeed Daniali
and David Cruz.

Danish Information Systems
Professionals, April 1998;
World Bridges in Denmark,
by Paul E. Bach

United States Naval
Academy — Bock Memorial
Lecture Series, Spring 1998;
***Offshore Construction for
the Next Millennium,***
by Ben C. Gerwick

University of San Diego,
Workshop on Materials for
Infrastructures, March 1998;
***Assessing the Remaining
Service Life of Structures in
the Marine Environment,***
by Ben C. Gerwick and
Sam Yao

International Bridge
Conference, June 1998;
***Eccentrically Braced and
Special Moment Resisting
Steel Frame Towers Support
Bridge Retrofit,***
by John M. Vincent and
Tore Abrahamsen

International Bridge
Conference, June 1998;
***Richmond-San Rafael Bridge
— Innovative Foundation
Retrofit,***
by Thomas Dahlgren and
John M. Vincent

Third International
Conference on Contract
Management, Singapore,
March 1998;
***The Role of Innovation in
Contract Management for
the Next Millennium,***
by Ben C. Gerwick


American Association of
Anaesthesiologists, May
1998;
***Seismic Retrofit of San
Francisco Bay Bridge,***
by Ben C. Gerwick

IABSE Colloquium on
Tunnel Structures, June 1998;
***Construction of Elements for
the Oresund Immersed
Tunnel,***
by R. Bittner, P. Nielsen,
L-G. Nilsson, C. Noren


Completion of the Presidio Viaduct Seismic Retrofit

The seismic retrofit of San Francisco's 59 year old Presidio Viaduct is now complete and the bridge may even look a little better than it did before construction started! Bents were strengthened using concrete jackets in combination with steel casings so that the architectural integrity of the bridge could be retained. By through-bolting high-strength bars, the reinforced concrete jackets are able to provide confinement as well as increased shear resistance. Integral shear keys at the elevation of the pinned bearing assemblies prevent bearing instability and a drop-type failure.

Included in the bearing retrofit were new longitudinal restrainer brackets embedded in the jackets.



Complete bent retrofit with concrete jackets and steel casings



High strength bars for concrete jacket retrofit

movement seismic isolation joint

The isolation joint provides a necessary separation between one of the 135-foot long deck-trusses and a concrete on-ramp that frames directly into the side of the

truss at midspan. Impacting between the two structures is prevented.

Plans and specifications for the retrofit were developed by Ben C. Gerwick, Inc. under an on-call contract with

the California Department of Transportation.

John M. Vincent



Bearing retrofit utilizing transverse shear key and longitudinal restrainer blanket

Bearing plates and U-bolts around the existing pins allow the brackets to resist push and pull movements. The bridge retrofit also required:

- truss end-frame strengthening
- bottom chord cable restrainers
- reinforced concrete footing overlays, and
- construction of a large-

Bath-Woolwich Bridge

Floating Cofferdams

Constructing bridge foundations under water is an expensive operation and usually represents 40 to 50% of the total bridge

the six main river piers. Figg's design for the piers was based on using 8-foot diameter drilled shafts. A typical pier foundation

block with the top of the footing about 3 ft below low tide. This design is very efficient because it significantly reduces the depth at which the footing is constructed. However, it does create the problem of how to construct an underwater footing suspended 28-foot off the river bottom.

In order to address this problem and reduce the amount of work in the river, Ben C. Gerwick, Inc. proposed the following construction sequence:

- Pre-install the drilled shafts using a two stage template.
- Construct a precast footing shell on shore and attach a temporary steel follower cofferdam.
- Launch the cofferdam and tow it to the bridge site.
- Position the cofferdam over the drilled shafts and fix it in position with 4 spud piles.
- Lower the cofferdam down over the pre-installed drilled shafts with jacks located on top of the spud piles.



Launch of concrete cofferdam

cost. One way of reducing this cost is to perform as much of the foundation work as possible on shore by prefabrication and then floating (or lifting) completed elements into position. With this objective in mind, Ben C. Gerwick, Inc. has been working closely with Flatiron Structures Company of Longmont, Colorado to design a floating cofferdam system for the Bath-Woolwich Bridge across the Kennebec River at Bath, Maine.

The Maine DOT awarded the design-construct contract for the 3,000-foot long 4 lane bridge to Flatiron and Figg Engineers in August of 1997, and shortly thereafter Ben C. Gerwick, Inc. was contacted by Flatiron to design a safe and economical cofferdam system for

will be located in 45 feet of water and will contain 4 drilled shafts supporting a 33-foot by 36-foot by 12-foot deep footing



Template for pre-installation of drilled shafts



Mating of follower cofferdam to floating precast footing shell


- Lock the footing to the drilled shafts by placing a 4-foot deep tremie seal.
- Dewater the cofferdam and construct the footing and pier shaft in the dry.
- Flood and remove the follower cofferdam for reuse on the next pier.

This construction sequence minimized work in the river and allowed the drilled shaft installation to proceed concurrently with the onshore fabrication and launch of the cofferdams.

Installation of the drilled shafts started in October 1997 and the first precast footing shell with follower cofferdam was launched April 28, 1998. The bridge is scheduled to be completed and

opened in late 1999 or early 2000.

Robert B. Bittner



Steel follower cofferdam assembled on barge

Monongahela River — Dam 2

Float-in Dam Construction

Ben C. Gerwick, Inc. is teamed with Bergmann Associates of Rochester, New York, and D'Appolonia of Pittsburgh, Pennsylvania, to design a replacement for Dam 2 on the Monongahela River for the US Army Corps of

through the elimination of conventional large sheetpile cofferdams and site dewatering,

- Shorter construction time by allowing concurrent construction of dam segments and dam foundations,

bays. The "In-the-Wet" construction plan calls for breaking the dam into two segments of 333-foot and 265-foot. The segments will be constructed as closed bottom boxes in a two level casting basin. The bottom of the boxes will be recessed for the pre-installed foundation caissons. As each segment is completed, it will be launched by flooding the basin and towed to the site for final outfitting. It will then be positioned over the foundation caissons with a mooring system mounted on the segment. Each segment will then be ballasted down onto 6 landing caissons

Dam positioned over pre-installed caissons



Completed dam in operation

Engineers. Ben C. Gerwick, Inc. has been working with the Corps Pittsburgh District for the last year, developing and evaluating innovative "In-the-Wet" construction techniques for building locks and dams on the lower Monongahela River.

"In-the-Wet" construction methods use off-site prefabrication combined with lift-in or float-in of large precast segments onto pre-installed foundations. The segments are locked onto the foundations by underbase grouting and infilling of the segments with tremie concrete. This method offers several advantages over conventional "In-the-Dry" construction:

- Less disruption to river navigation and river flow,
- Lower cost of construction

- Less environmental impact by reducing dredging and elimination of site dewatering,
- Higher quality by allowing the use of precast concrete produced in a controlled environment.

Ben C. Gerwick, Inc. is taking the lead in designing of the pre-cast dam segments and developing the construction methods and procedures for:

- Casting and launching of the pre-cast dam segments,
- Transport, positioning and immersion of the segments on to the pre-installed foundations,
- Underbase grouting and tremie in-fill of the segments.

The new dam will be a 600-foot long structure with four gate

and leveled with flat jacks. The pile tops and underbase will be grouted, and 8-foot of tremie concrete will be placed in the segment. Each segment will then be dewatered and the remainder of the dam including tainter gates will be completed in the dry.

The final plans and specifications will be completed in October of 1998. Construction is scheduled to start in the Spring of 1999 and be completed in 2002.

Robert B. Bittner

Llagas Creek Bridge Replacement

Staged New Construction



Abutment at "T" intersection

Staged construction and a temporary signalized "T" intersection with two-way traffic over a one-lane bridge is allowing a narrow, three-span structure built in the early 1920's to be replaced with a wider single-span, post-tensioned box girder that's offset from the original alignment by only 4.5 feet. Impacts to neighboring properties and the riparian habitat are thereby minimized.

Cast-in-place construction above the creek is taking place during the usually restricted "wet" season by utilizing steel falsework beams on bents specifically designed to resist flood-stage stream pressures. The bottom of the beams are more than two feet above the design flood water surface to reduce the potential for damage from floating debris during construction. By excluding permanent bents within the creek and adding rock slope protection in front of the abutments, the single-span bridge essentially eliminates long-term

maintenance concerns below the roadway deck.

Ben C. Gerwick, Inc., selected by the County of Santa Clara Roads and Airports Department to manage a consultant team providing structural, civil, traffic, electrical, hydrological and geotechnical design services, was directly responsible for the bridge type selection and final design. The bridge was designed for a peak rock acceleration of 0.5g resulting from either a magnitude 7.5 earthquake on the Calaveras Fault or a magnitude 8.0 on the San Andreas Fault. The Calaveras Fault is within 5.5 miles of the bridge site.

To ensure stability during the first construction stage an internal abutment shear key was added to the girder to

compensate for the missing external key. In addition, an internal abutment wall supplemented the outside wingwall to fully engage the abutment backfill. This protected the short steel H-piling from excessive demands. The internal wall also compensates for the lower resistance resulting from the tightly curved wingwalls used to accommodate turning movements at the "T" intersection.

One of the most challenging features of a small bridge replacement project is "fitting" the structure into the site. The Llagas Creek Bridge Replacement was no exception. Special attention had to be given to the close proximity of the intersection and the need to maintain traffic at all times. The turning radius of the County's articulated bus fleet had to be accommodated while at the same time ensuring there would be sufficient space for



Support bents installed for Stage 2 construction

driving piles and constructing the abutment adjacent to the intersection.

John M. Vincent

LNG Storage

Floating Concrete Structures

In 1997 Ben C. Gerwick, Inc. conducted a study for Mobil Technology Company, to determine the structural feasibility of storing Liquefied Natural Gas, LNG, in concrete structures afloat in the ocean. LNG reduces the volume of natural gas by approximately 600 times, by liquefying natural gas at approximately -261°F (-163°C). This reduction in volume makes it practicable to transport natural gas from remote gas fields to markets across the ocean. While steel vessels are normally used for the storage and transport of LNG, the use of stationary concrete structures would have several advantages in the way of economy and durability. However, before these advantages can be realized, it must be demonstrated that monolithic concrete structures can resist the thermal stresses/strains associated with the very low temperatures of LNG; which was the objective of the study.


The use of monolithic joints in concrete tanks offers both practical benefits and technical difficulties. The benefits include simplified construction, ability to resist loads across the joint, and potentially reduced costs. The difficulties center around the thermally induced stresses within the joint, which can cause failure of the joint, for certain types of joint design. Thermal stresses consist of two broad categories:

- 1) Internally induced stresses;
- and 2) Externally induced



Topside configuration

stresses. The internal stresses are induced by non-linear thermal gradients through an elastic member, which is trying to deform linearly (i.e. plane sections remaining plane).



FEM model for thermal strain

The external stresses (axial, moment, shear) obviously come from external restraint of thermally induced contractions (expansions). In addition to these considerations, it should be noted that both internally-

induced, and externally-induced, stresses can be relieved and/or redistributed within the member, by appropriate deformation of the member including sliding, bending, or cracking of the concrete.

3-D finite element models of appropriate concrete structures were developed for both primary, and secondary, LNG containment cases. These models clearly indicated that both primary, and secondary, concrete containment structures would sustain excessive thermal stresses if conventionally configured with right angled joints, and conventionally reinforced. However, these models also indicated, that with practicable modifications to both both configuration and reinforcing, it should be feasible to construct both primary, and secondary, large stationary concrete floating containment structures. These modification include careful selection of materials, geometry, prestressing, liners, insulation, restraint conditions and reinforcing steel layouts.

Dale E. Berner